

KALOSONJE WATER PAN

20/05/2026

BUDGET ESTIMATE:

Excavator

Mobilization - to and from - 100,000

Hours - 150 hrs x 5000 = 750,000

Fuel - 1500 ltr x 245 = 367,500

Operator allowance = 3000 x 15 = 45000

1,262,500

LORRIES

Hire - 15000 x 12 x 2 = 360,000

Fuel = 40 ltr x 245 x 12 x 2 = 235,200

Drivers allowance = 2000 x 12 x 2 = 48000

643,200

Casuals & skilled wages

Skilled - 2 x 1000 x 20 = 40,000 (Foreman/surveyor)

Unskilled - 5 x 500 x 20 = 50,000

Engineer - 2500 x 20 = 50,000

140,000

Fencing

Posts - 133 x 2000 = 266,000

Chainlink - 22 rolls x 3500 = 77,000

Barbed wire - 1 roll x 6000 = 6,000

Labour = 100,000

449,000

GATE

Fabrication - 50,000

499,000

Spillway Construction = 240,000

labour

Sub TOTAL = 2,784,700

Allow 100,000 for miscellaneous

Grand total = 2,884,700

Typical cross-section
of the pan:

